

SECTION 09 67 23-RESINOUS FLOORING

PROSHIELD SC-100- Three Coat- 20-40 mil Thickness, Pigmented Epoxy/Polyaspartic/Urethane System

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This section includes the following:
 - 1. Resinous flooring system as shown on the drawings and in schedules.
- B. Related sections include the following:
 - 1. Cast-in-Place Concrete, section 03 30 00
 - 2. Concrete Curing, section 03 39 00

1.3 SYSTEM DESCRIPTION

- A. The work shall consist of preparation of the substrate, the furnishing and application of a 100% solids Epoxy Primer, a pigmented 100% Solids Epoxy Body Coat, or alternatively for a “Fastrack” application, a Polyaspartic Body Coat, and a top coat of Pigmented or Clear High Performance Urethane.
- B. The system shall have the color and texture as specified by the Owner with a nominal thickness of 20-40 mils (application thickness is based on recommended min. or max. levels for each coating application). It shall be applied to the prepared area(s) as defined in the plans strictly in accordance with the Manufacturer’s recommendations.
- C. Cove base (if required) to be applied where noted on plans and per manufacturers standard details unless otherwise noted.

1.4 SUBMITTALS

- A. Product Data: Latest edition of Manufacturer’s literature including performance data and installation procedures.
- B. Manufacturer’s Safety Data Sheet (SDS) for each product being used.
- C. Samples: A 6-inch square sample of the proposed system. Color, texture, and thickness shall be Representative of overall appearance of finished system.
- D. LEED Submittals:
 - 1. Product data for Credit EQ 4.2: For flooring system, documentation including VOC content and chemical composition.
 - 2. MR Credit 2.1, 2.2: Construction waste management, packaging can be recycled.

1.5 QUALITY ASSURANCE

- A. The Manufacturer shall have a minimum of 5 years' experience in the production, sales, and technical support of epoxy and urethane industrial flooring and related materials.
- B. The Applicator shall have been approved by the flooring system manufacturer in all phases of surface preparation and application of the product specified.
- C. No requests for substitutions shall be considered that would change the generic type of the specified System.
- D. System shall be in compliance with requirements of United States Department of Agriculture (USDA), Food & Drug Administration (FDA), and local Health Department.
- E. A pre-installation conference shall be held between Applicator, General Contractor and the Owner for review and clarification of this specification, application procedure, quality control, inspection and acceptance criteria and production schedule.

1.6 PRODUCT DELIVERY, STORAGE, AND HANDLING

- A. Packaging and Shipping
 - 1. All components of the system shall be delivered to the site in the Manufacturer's packaging, clearly identified with the product type and batch number.
- B. Storage and Protection
 - 1. The Applicator shall be provided with a storage area for all components. The area shall be between 60°F and 85°F, dry, out of direct sunlight and in accordance with the Manufacturer's recommendations and relevant health and safety regulations.
 - 2. Copies of Safety Data Sheets (SDS) for all components shall be kept on site for review by the Engineer or other personnel.
- C. Waste Disposal
 - 1. The Applicator shall be provided with adequate disposal facilities for non-hazardous waste generated during installation of the system.

1.7 PROJECT CONDITIONS

- A. Site Requirements
 - 1. Application may proceed while air, material and substrate temperatures are between 60°F and 85°F providing the substrate temperature is above the dew point. Outside of this range, the Manufacturer shall be consulted.
 - 2. The relative humidity in the specific location of the application shall be less than 85% but no less than 30% and the surface temperature shall be at least 5°F above the dew point.
 - 3. The Applicator shall ensure that adequate ventilation is available for the work area.
 - 4. The Applicator shall be supplied with adequate lighting equal to the final lighting level during the preparation and installation of the system.
- B. Conditions of New Concrete to Receive Coating
 - 1. Concrete shall be moisture cured for a minimum of 7 days and have fully cured a minimum of twenty-eight days in accordance with ACI-308 prior to the application of the coating system pending moisture tests.
 - 2. Concrete shall have a flat rubbed finish, float or light steel trowel finish (a hard steel trowel finish is neither necessary nor desirable).
 - 3. Sealers and curing agents should not to be used.
 - 4. Concrete surfaces on grade shall have been constructed with a vapor barrier to protect against the effects of vapor transmission and possible delamination of the system.

- C. Safety Requirements
 - 1. All open flames and spark-producing equipment shall be removed from the work area prior to commencement of application.
 - 2. "No Smoking" signs shall be posted at the entrances to the work area.
 - 3. The Owner shall be responsible for the removal of foodstuffs from the work area.
 - 4. Non-related personnel in the work area shall be kept to a minimum.

1.8 WARRANTY

- A. ProREZ Performance Resins & Coatings warrants that material shipped to buyers at the time of shipment substantially free from material defects and will perform substantially to ProREZ Performance Resins & Coatings published literature if used in accordance with the latest prescribed procedures and prior to the expiration date.
- B. ProREZ Performance Resins & Coatings liability with respect to this warranty is strictly limited to the value of the material purchase.
- C. ProREZ Performance Resins & Coatings has no responsibility for the application and processing of products and is under no circumstances liable to any third party whatsoever.

PART 2 – PRODUCTS

2.1 FLOORING- ProREZ Performance Resins & Coatings: ProShield SC-100- 20-40 mils, Pigmented Epoxy or Polyaspartic Flooring System with High Performance Topcoat

- 1. System Materials:
 - a. Primer: ProREZ Performance Resins & Coatings, ProPoxy S-Resin (Clear) and Hardener. In the event of elevated moisture levels exceeding 5lbs (calcium chloride) or 82% RH (Insitu Probe) then replace ProPoxy S system with ProPoxy MB (S or F) moisture mitigating primer. See data sheet.
 - b. Base/Body Coat: Option #1- Epoxy - ProREZ Performance Resins & Coatings, ProPoxy S-Resin (Pigmented) & Hardener
Option #2 –Polyaspartic- ProREZ Performance Resins & Coatings, ProSpartic S-Resin (Pigmented) and Hardener.
Topcoat: ProREZ Performance Resins & Coatings, ProThane S, F, or HH Resin (Clear or Pigmented) and Hardener. See data sheet.
- 2. Patch Materials
 - a. Shallow /Deep Fill and Patching: Use ProPoxy S-Resin & Hardener with clean dry silica sand suitable for troweling.

2.2 MANUFACTURER

- A. ProREZ Performance Resins & Coatings P.O. Box 153, Cromwell, CT06416-0153.
- B. Manufacturer of Approved System shall be single source and made in the USA.

2.3 PRODUCT REQUIREMENTS

A.	Primer	ProPoxy S or ProPoxy MB
B.	Base Coat	ProPoxy S
1.	Percent Solids	100 %
2.	VOC	0 g/L
3.	Tensile Strength, ASTM D 638	5,780 psi
4.	Abrasion Resistance, ASTM D 4060 C 17 Wheel, 1,000 gm load, 1,000 cycles	30mg weight loss
5.	Flammability, ASTM D 684, NFPA 101, Type 1	Class 1
6.	Hardness, Shore D ASTM 2240	70-80
7.	Potlife @ 70 F	20-40 minutes
C.	Top Coat	ProThane S or F
1.	Tensile Strength ASTM D-2370	6,500 psi
2.	Adhesion ASTM D-4541	400 psi, concrete failure (applied over epoxy)
4.	Abrasion Resistance 1000 GM Load 1000 Cycles ASTM D-4060	10-15 mg loss

PART 3 – EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas and conditions, with Applicator present, for compliance with requirements for maximum moisture content, installation tolerances and other conditions affecting flooring performance.
 1. Verify that substrates and conditions are satisfactory for flooring installation and comply with requirements specified.

3.2 PREPARATION

- A. General
 1. New and existing concrete surfaces shall be free of oil, grease, curing compounds, loose particles, moss, algae growth, laitance, friable matter, dirt, and bituminous products.
 2. Verify that the concrete substrate(s) are dry to accept the resinous flooring system using one of the following standard test methods for determining relative levels of dryness/wetness:
 - a. Perform most current version of internal relative humidity ("in situ") probe test in general conformance with ASTM F2170. Proceed with the resinous flooring application only when the substrate(s) does not exceed a maximum potential equilibrium relative humidity of 75 percent.
 - b. Perform most current version of anhydrous calcium chloride test in general conformance with ASTM F1869. Proceed with the resinous flooring application only when the substrate(s) measures moisture-vapor emission rates less than 5lbs/1,000s.f./24hrs.
 - c. If the relative "wetness" of the substrate(s) exceeds the manufacturer's guidelines, then the Owner and/or Engineer shall be notified and advised of additional cost for the possible installation of a moisture-vapor mitigation system that has been approved by the manufacturer or other means to lower the substrate "wetness" value to the acceptable limit.

3. There shall be no visible moisture present on the surface at the time of application of the system. Compressed oil-free air and/or a light passing of a propane torch may be used to dry the substrate.
4. Mechanical surface preparation
 - a. Shot blast all surfaces to receive flooring system with a mobile steel shot, dust recycling machine (Blastrac or equal). All surface and embedded accumulations of paint, toppings hardened concrete layers, laitance, power trowel finishes and other similar surface characteristics shall be completely removed leaving a bare concrete surface having a minimum profile of CSP 3-4 as described by the International Repair Institute.
 - b. Floor areas inaccessible to the mobile blast machines shall be mechanically abraded to the same degree of cleanliness, soundness and profile using diamond grinders, needle, bush hammers, or other suitable equipment.
 - c. Cracks and joints (non-moving) greater than 1/8 inch wide are to be chiseled or chipped-out and repaired per manufacturer's recommendations.
5. Patching
 - a. At spalled or worn areas, mechanically remove loose or delaminated concrete to a sound concrete and patch per manufactures recommendations.

3.3 APPLICATION

A. General

1. The system shall be applied in five distinct steps as listed below:
 - a. Substrate preparation
 - b. Priming
 - c. Base/Body coat application
 - d. Topcoat application
2. Immediately prior to the application of any component of the system, the surface shall be dry and any remaining dust or loose particles shall be removed using a vacuum or clean, dry, oil-free compressed air.
3. The handling, mixing and addition of components shall be performed in a safe manner to achieve the desired results in accordance with the Manufacturer's recommendations.
4. The system shall follow the contour of the substrate unless pitching or other leveling work has been specified by the Architect.
5. A neat finish with well-defined boundaries and straight edges shall be provided by Applicator.

B. Primer (Clear)

1. The primer shall comprise of 2 components, resin and hardener as supplied by the Manufacturer (mix ratio = 3 parts resin to 1 part hardener).
2. In the event of elevated moisture levels the primer shall comprise of 2 components, resin and as supplied by the Manufacturer (mix ratio = 2 parts resin to 1 part hardener) for ProProxy MB, MoistureBLOK.
3. The hardener shall be added to the resin and thoroughly mixed by suitably approved low speed drill mixer.
4. The primer shall be applied over horizontal surfaces using flat or 1/8" notched squeegee and 3/8" nap roller as approved by the Manufacturer- average coverage rate = 100-200s.f./per gal using ProProxy S, or 100s.f./per gal when using ProProxy MB, MoistureBLOK primer.
5. Allow material to fully cure.

- C. Base/Body Coat (Pigmented)
 - 1. The Base/Body coat shall comprise of 3 components, a resin and hardener and pigment as supplied by the Manufacturer.
 - Option 1- ProREZ ProPoxy S pigmented Epoxy resin, hardener mix ratio = 3 parts resin to 1 part hardener and ProColor colorant at 8oz per gal.
 - Option 2- ProREZ ProSpartic S pigmented Polyaspartic resin, hardener mix ratio = 1 parts resin to 1 part hardener and ProColor colorant at 8oz per gal.
 - 2. The hardener shall be added to the resin together with colorant and thoroughly mixed by suitably approved low speed drill mixer.
 - 3. The Base/Body coat shall be applied over horizontal surfaces using suitable squeegee and 3/8" roller nap as approved by the Manufacturer.- average coverage rate = 100-200s.f./per gal.
 - 4. Allow material to fully cure.
- D. Top Coat (Clear or Pigmented)
 - 1. The pigmented gloss topcoat shall comprise of 3 or 4 components, resin, hardener, colorant, and, if required, optional aluminum oxide grit for additional abrasion and non-slip resistance, as supplied by the Manufacturer (mix ratio = 1 part resin to 2 parts hardener).
 - 2. The hardener shall be added to the resin and thoroughly mixed by suitably approved low speed drill mixer.
 - 3. The Top Coat shall be applied over horizontal surfaces from a roller tray using a 3/8" Roller as approved by the Manufacturer- coverage rate = 400- 600s.f./per gal.
 - 4. Allow the material to fully cure.
 - 5. The finished floor will have a nominal thickness of 20-40 mils.

3.4 FIELD QUALITY CONTROL

- A. Tests, Inspection
 - 1. The following tests shall be conducted by the Applicator:
 - a. Temperature
 - 1. Air, substrate temperatures and, if applicable, dew point.
 - b. Coverage Rates
 - 1. Rates for all layers shall be monitored by checking quantity of material used against the area covered.

3.5 CLEANING AND PROTECTION

- A. Cure flooring material in compliance with manufacturer's directions, taking care to prevent their contamination during stages of application and prior to completion of the curing process.
- B. Remove masking. Perform detail cleaning at floor termination, to leave cleanable surface for subsequent work of other sections.